



• 39352 221st Avenue • Le Center, MN 56057 • Telephone (507) 357-6463 • Facsimile (507) 357-6096 •

Attention: MBE/WBE Subcontractors and Suppliers

Subject: Request for Quote

Ti-Zack Concrete, LLC will be bidding on the project(s) listed below and would like to receive a quote from your company.

Project Owner: Hennepin County

Bid Date & Time: 11/10/2026 @ 2:00 PM

Project Information: #2164000R – CSAH 52 Hennepin Ave Bridge Rehabilitation-Rebid

Goal: MBE 10%/WBE 10%

Items of work include but are not limited to bridge cable repair and wrapping, bridge painting, traffic control, electrical, erosion control pavement marking, sawing surveying, signing, field office and material supply. Please review the attached bid form(s) and contact me if you are interested in bidding on this(these) project(s) and need more information to be able to supply a quote. I will happily forward you the necessary information.

Please provide quotes by **5pm on 11/09/2026**.

Please note the following:

Ti-Zack Concrete, LLC will be open to subcontracting portions of all the work to increase the likelihood that the MBE/WBE goal will be achieved and is willing to break out the contract work into economically feasible units and/or allow MBE/WBEs to perform all or portions of the work that it may normally perform itself.

An items list is attached and project plans may be found on the Hennepin County website <https://hennepin.procureware.com/Bids/2a4878b4-6611-4fbb-b01a-a60efbaaf2da?t=Description> or you may contact me at estimating@tizack.com for a link. Please let us know if you need additional information about plans, specifications, and requirements of the contract.

Ti-Zack Concrete, LLC will make efforts to assist interested MBE/WEB in obtaining bonding, lines of credit or insurance as required by the Department or the Prime.

Ti-Zack Concrete, LLC will also assist in obtaining necessary equipment, supplies, materials or related assistance or services as required by the Owner or the contractor.

Thank you.

Dave Collins, Estimator

Hennepin Co CSAH 52 - Hennepin Ave

1	2011.601/01000	AS BUILT	1	LUMP SUM
2	2013.602/00051	TCLP TEST	2	EACH
3	2021.501/00010	MOBILIZATION	1	LUMP SUM
4	2031.502/00010	FIELD OFFICE	1	EACH
5	2102.503/00010	PAVEMENT MARKING REMOVAL	23,330.00	LIN FT
6	2102.518/00010	PAVEMENT MARKING REMOVAL	395	SQ FT
7	2104.502/01000	REMOVE LIGHT POLE	12	EACH
8	2104.502/01220	REMOVE SIGN	7	EACH
9	2104.503/00195	SAWING CONCRETE PAVEMENT (FULL DEPTH)	60	LIN FT
10	2104.518/00140	REMOVE CONCRETE WALK	271	SQ FT
11	2104.601/01350	REMOVE REGULATED WASTE MATERIAL (BRIDGE)	1	LUMP SUM
12	2123.610/00410	STREET SWEEPER (WITH PICKUP BROOM)	80	HOURL
13	2211.507/00170	AGGREGATE BASE (CV) CLASS 5	6	CU YD
14	2401.518/03647	RAISED MEDIAN CONCRETE (3S52)	4,128.00	SQ FT
15	2401.618/00002	SPECIAL SURFACE FINISH (INPLACE)	42,255.00	SQ FT
16	2404.618/00399	CONCRETE WEARING COURSE (CHOICE)	94,056.00	SQ FT
17	2411.508/00011	REINFORCEMENT BARS (EPOXY COATED)	1,580.00	POUND
18	2411.618/00030	STONE MASONRY VENEER	35	SQ FT
19	2433.502/00050	ANCH TYPE REINF BARS (TYPE L)	1,664.00	EACH
20	2433.506/00100	SEAL CRACKS WITH EPOXY BY CHASE METHOD	30	GALLON
21	2433.518/00008	REMOVE CONCRETE WEARING COURSE	94,056.00	SQ FT
22	2433.601/10001	CLEAN AND PAINT VERTICAL SUSPENDER ROPES	1	LUMP SUM
23	2433.601/10002	IMPROVE EXPANSION WIND RESTRAINT	1	LUMP SUM
24	2433.601/10003	REPLACE UPLIFT BEARINGS	1	LUMP SUM
25	2433.601/10004	RE-WRAP & SEAL MAIN CABLE	1	LUMP SUM
26	2433.601/10005	SEAL STIFFENING GIRDER OPENING	1	LUMP SUM
27	2433.601/10006	STIFFENING GIRDER BEARING AND FENDER	1	LUMP SUM
28	2433.601/10007	TEMPORARY ACCESS - MAIN CABLES	1	LUMP SUM
29	2433.602/10001	ANCHORAGE DEHUMIDIFICATION	6	EACH
30	2433.602/10002	GREASE ROCK ANCHORS	112	EACH
31	2433.602/10003	GREASE TENSION ROD	152	EACH
32	2433.602/10004	LIFT OFF TEST OF ANCHORAGE ANCHOR RODS	12	EACH
33	2433.602/10005	MEASURE, DETENSION, INSPECT, RETENSION CABLE BOLT BANC	1,136.00	EACH
34	2433.602/00205	MODIFY DRAINAGE SYSTEM	1	EACH
35	2433.602/00044	RECONSTRUCT BEARING ASSEMBLY	6	EACH
36	2433.602/10006	REGLAZE & SEAL TOWER WINDOW	6	EACH
37	2433.602/10007	TOWER TOP SEALING	6	EACH
38	2433.603/01909	RECONSTRUCT EXPANSION JOINT TYPE 9	240	LIN FT
39	2433.603/02010	RECONSTRUCT EXPANSION JOINT TYPE A	467	LIN FT
40	2433.603/02090	RECONSTRUCT EXPANSION JOINT TYPE SPECIAL	18	LIN FT
41	2433.603/00036	REPAIR STRUCTURAL CRACKS	8	LIN FT
42	2433.618/00110	CONCRETE SURFACE REPAIR	850	SQ FT
43	2433.618/00056	REMOVE AND PATCH SLAB TYPE A	4,500.00	SQ FT
44	2433.618/00057	REMOVE AND PATCH SLAB TYPE B	2,700.00	SQ FT
45	2433.618/00058	REMOVE AND PATCH SLAB TYPE C	1,800.00	SQ FT
46	2473.503/00040	EXPANSION JOINT DEVICES TYPE 4	467	LIN FT
47	2473.503/00109	MODULAR BRIDGE JOINT SYSTEM TYPE 9	240	LIN FT

48	2476.601/00050	WASTE COLLECTION AND DISPOSAL	1	LUMP SUM
49	2478.518/00030	ORGANIC ZINC-RICH PAINT SYSTEM (OLD)	336,815.00	SQ FT
50	2478.618/00010	CLEAN AND PAINT STEEL	614	SQ FT
51	2521.518/00040	4" CONCRETE WALK	271	SQ FT
52	2533.503/03010	PORTABLE PRECAST CONCRETE BARRIER DESIGN 8337	2,050.00	LIN FT
53	2533.503/03030	RELOCATE PORTABLE PRECAST CONCRETE BARRIER DESIGN 8337	2,050.00	LIN FT
54	2545.602/00100	LIGHTING UNIT TYPE SPECIAL	12	EACH
55	2545.602/14051	LUMINAIRE (LED) A	8	EACH
56	2545.602/14052	LUMINAIRE (LED) B	30	EACH
57	2563.601/00001	TRAFFIC CONTROL SUPERVISOR	1	LUMP SUM
58	2563.601/00010	TRAFFIC CONTROL	1	LUMP SUM
59	2563.601/00100	ALTERNATE PEDESTRIAN ROUTE	1	LUMP SUM
60	2563.602/00035	PORTABLE BARRIER DELINEATOR	82	EACH
61	2563.602/01100	PORTABLE CHANGEABLE MESSAGE SIGN	2	EACH
62	2563.615/00010	TEMPORARY IMPACT ATTENUATOR	2	ASSEMBLY
63	2563.615/00020	RELOCATE TEMPORARY IMPACT ATTENUATOR	2	ASSEMBLY
64	2563.618/00011	CONSTRUCTION SIGN-SPECIAL	100	SQ FT
65	2564.518/00010	SIGN	30	SQ FT
66	2564.518/00020	SIGN PANEL	18	SQ FT
67	2564.602/01505	SIGN COLLAR	7	EACH
68	2564.602/02380	DELINEATOR TYPE SPECIAL	82	EACH
69	2573.501/00030	EROSION CONTROL SUPERVISOR	1	LUMP SUM
70	2573.502/00110	STORM DRAIN INLET PROTECTION	42	EACH
71	2575.501/00020	TURF ESTABLISHMENT	1	LUMP SUM
72	2581.503/00006	6" REMOVABLE PREFORMED PAVEMENT MARKING TAPE	28,639.00	LIN FT
73	2581.603/00020	REMOVABLE PREFORMED PLASTIC MASK (BLACK)	3,884.00	LIN FT
74	2582.503/10106	6" SOLID LINE PAINT	9,186.00	LIN FT
75	2582.503/10108	8" SOLID LINE PAINT	289	LIN FT
76	2582.503/10124	24" SOLID LINE PAINT	112	LIN FT
77	2582.503/10206	6" BROKEN LINE PAINT	1,690.00	LIN FT
78	2582.503/10306	6" DOTTED LINE PAINT	210	LIN FT
79	2582.503/58106	6" SOLID LINE PREFORM TAPE GROUND IN CONTRAST	1,921.00	LIN FT
80	2582.503/58206	6" BROKEN LINE PREFORM TAPE GROUND IN CONTRAST	450	LIN FT
81	2582.503/58306	6" DOTTED LINE PREFORM TAPE GROUND IN CONTRAST	206	LIN FT
82	2582.503/80124	24" SOLID LINE PREFORM THERMO GROUND IN CONTRAST	125	LIN FT
83	2582.503/57106	6" SOLID LINE PREFORM TAPE CONTRAST	7,278.00	LIN FT
84	2582.503/57206	6" BROKEN LINE PREFORM TAPE CONTRAST	1,130.00	LIN FT
85	2582.503/57306	6" DOTTED LINE PREFORM TAPE CONTRAST	120	LIN FT
86	2582.503/57108	8" SOLID LINE PREFORM TAPE CONTRAST	289	LIN FT
87	2582.518/04060	PAVEMENT MESSAGE PREFORM THERMOPLASTIC GROUND IN CONTRAST	134	SQ FT
88	2582.618/09000	PAVEMENT MARKING SPECIAL	537	SQ FT
89	2582.518/08070	CROSSWALK PREFORM THERMOPLASTIC GROUND IN CONTRAST	870	SQ FT