PCiRoads, LLC
7865 Jefferson Highway
Maple Grove, MN 55369-4900
Telephone: 763.497.6100 / Fax: 763.497.6101
www.pciroads.com

To: Subcontractors and Suppliers

From: PCiRoads, LLC

City of Saint Paul, Event 1750, 2026 Citywide Sewer Repairs, City Project 26-S-2099 in Ramsey Co
Bids: 11/10/26 at 2:00 PM

PCiRoads, LLC will be bidding on the above-mentioned project and requests quotes for all available work. Please use the above description when submitting quotes. See the attached package for details.

Bids	Project	Goal
11/10	**City of St. Paul, 1750, 2026 Citywide Sewer Repairs, CP 26-S-2099, Ramsey Co**	**VOP Participation** CERT-Certified SBE, WBE, and MBE firms

- All or any part of the bid items will be accepted and considered for the project. All quotes should include all incidental items except as noted in your quote. We are prepared to assist you in project scheduling, preparing proposals, pit and batch plant locations, interpreting plans and specifications, bonding and insurance needs, equipment, materials, and any other areas you may have questions about. Please note on your quote whether items are tied or not. Also, please include line number, description, quantity, and unit price for each item as well as a grand total. Please contact Erica Rekstad, 763-497-6100 or erica.rekstad@pciroads.com with any questions.

- Plans are available from the St. Paul Supplier Portal - Event 1750-0 Summary / Supplier Portal, by calling Erica Rekstad at 763-497-6216, or via email at estimating@pciroads.com.

- Please provide quotes 5 pm day before letting.

For VOP Participation Credit, firms must be currently CERT-certified for the proposed work. The CERT service includes the following Minnesota counties: Anoka, Benton, Carver, Chisago, Dakota, Hennepin, Isanti, Ramsey, Scott, Sherburne, Stearns, Washington, and Wright. It also includes the following Wisconsin counties: Pierce & St. Croix.

Thank you for your time and consideration. I look forward to hearing from you.

Sincerely,
Erica Rekstad
PCiRoads, LLC

AN EQUAL OPPORTUNITY EMPLOYER

CITY OF SAINT PAUL

DEPARTMENT OF PUBLIC WORKS

PLANS AND SPECIFICATIONS

FOR

2026 Citywide Sewer Repairs

CITY PROJECT 26-S-2099

I herby certify that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

Nathan Florek
Signature

Nathan C. Florek
Name

9/25/2026 63801
Date License No.

2026 CITYWIDE SEWER REPAIRS PROJECT (Event #1750)
SAINT PAUL PW SEWER UTILITY, CITY PROJECT 26-S-2099

BID SCHEDULE

MAJOR SEWER REPAIR SITES (CITYWIDE)

No.	Item	Description	Unit	Quantity	Unit Price	Cost
1.	1710.601	TRAFFIC CONTROL	LUMP SUM	1	$0.00	$0.00
2.	2021.501	MOBILIZATION (5% MAXIMUM)	LUMP SUM	1	$0.00	$0.00
3.	2104.603	REMOVE PIPE SEWERS	LINEAR FOOT	36	$0.00	$0.00
4.	2104.503	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	LINEAR FOOT	510	$0.00	$0.00
5.	2104.504	REMOVE PAVEMENT	SQ. YD.	680	$0.00	$0.00
6.	2108.504	GEOTEXTILE FABRIC TYPE V	SQ. YD.	330	$0.00	$0.00
7.	2123.610	STREET SWEEPING (WITH PICKUP BROOM)	HOUR	16	$0.00	$0.00
8.	2211.507	AGGREGATE BASE PLACED (CV), CLASS 5 (P)	CU. YD.	120	$0.00	$0.00
9.	2301.607	LEAN MIX BACKFILL - ABANDON SEWERS IN-PLACE	CU. YD.	1.0	$0.00	$0.00
10.	2360.509	TYPE SP WEB340F WEARING COURSE MIX (3,B) 2" THICK	TON	150	$0.00	$0.00
11.	2451.609	GRANULAR PIPE BEDDING	TON	260	$0.00	$0.00
12.	2451.609	AGGREGATE FOUNDATION FOR SEWERS	TON	25	$0.00	$0.00
13.	2475.602	ANCHOR BOLTS AND HARDWARE	EACH	32	$0.00	$0.00
14.	2475.608	TUBULAR RAILING ASSEMBLY	POUNDS	530	$0.00	$0.00
15.	2503.503	16" P.V.C. PIPE SEWER, C900 (DR 14)	LINEAR FOOT	36	$0.00	$0.00
16.	2503.601	CONSOLIDATION GROUTING	LUMP SUM	1	$0.00	$0.00
17.	2503.601	TEMPORARY CONVEYANCE	LUMP SUM	1	$0.00	$0.00
18.	2503.602	SANITARY SEWER SERVICE REPAIR EXCAVATION	EACH	1	$0.00	$0.00
19.	2503.602	INSTALL SEWER COUPLING	EACH	2	$0.00	$0.00
20.	2503.602	TELEVISE REPAIRED SEWER SERVICES (LATERAL LAUNCH FROM SEWER MAIN)	EACH	1	$0.00	$0.00
21.	2503.603	SANITARY SEWER SERVICE REPAIR	LINEAR FOOT	24	$0.00	$0.00
22.	2503.603	CLEAN AND TELEVISE SANITARY SEWER	LINEAR FOOT	263	$0.00	$0.00
23.	2506.502	ADJUST FRAME AND RING CASTING	EACH	1	$0.00	$0.00
24.	2506.502	CASTING ASSEMBLY	EACH	1	$0.00	$0.00
25.	2506.601	FURNISH AND CONSTRUCT MANHOLE (SNM-905274, SPECIAL)	LUMP SUM	1	$0.00	$0.00
26.	2506.601	CONSTRUCT MANHOLE, TYPE II (30" I.D.)	EACH	1	$0.00	$0.00
27.	2506.602	FURNISH AND DELIVER R-2560-E1, (NF-2560483) GRATE ONLY, SEE APPENDIX D	EACH	4	$0.00	$0.00
28.	2506.602	FURNISH AND DELIVER R-1733, 7" (NF-17332007) FRAME ONLY, SEE APPENDIX D	EACH	10	$0.00	$0.00
29.	2506.602	FURNISH AND DELIVER CINC-774E ADJUSTING RING (NF-00000034), SEE APPENDIX D	EACH	50	$0.00	$0.00

30.	2506.602	FURNISH AND DELIVER R-1678-A ADJUSTING RING W/ 1" RISE (NF-1979 T64), SEE APPENDIX D	EACH	100	$0.00	$0.00
31.	2507.603	CENTRIFUGALLY CAST LINING MANHOLES	LINEAR FOOT	18	$0.00	$0.00
32.	2507.603	CENTRIFUGALLY CAST LINING PIPES	LINEAR FOOT	25	$0.00	$0.00
33.	2557.602	SWING GATE	EACH	2	$0.00	$0.00
34.	2557.603	BOTTOM BRACE RAIL	LINEAR FOOT	40	$0.00	$0.00
35.	2573.502	STORM DRAIN INLET PROTECTION	EACH	4	$0.00	$0.00
36.	****	ALLOWANCE TO PRE-CLEAN SANITARY PIPES (TIME AND MATERIAL)	****	****	$10,000.00	$10,000.00
37.	****	ALLOWANCE TO RAISE MANHOLE CASTINGS TO SURFACE (TIME AND MATERIAL)	****	****	$50,000.00	$50,000.00
38.	****	ALLOWANCE FOR SEWER REPAIRS (TIME AND MATERIAL)	****	****	$100,000.00	$100,000.00
39.	****	ALLOWANCE FOR POTHOLING UTILITIES (TIME AND MATERIAL)	****	****	$80,000.00	$80,000.00
					Total Project Bid ($)	**$240,000.00**